



- GENERAL NOTES:**
1. ALL DIMENSIONS ARE TO FACE OF STUD, CMU OR CONCRETE UNLESS NOTED OTHERWISE.
 2. PROVIDE WOOD BLOCKING, AS REQUIRED, IN WALLS AND CEILINGS TO ANCHOR ALL WALL AND CEILING-MOUNTED ITEMS, INCLUDING BUT NOT LIMITED TO, MILLWORK/CASEWORK, WALL CABINETS, HANDRAILS, COAT RACKS, DOOR STOPS, OWNER EQUIPMENT, SHELVING, AND OTHER SIMILAR ITEMS.
 3. USE GYP BOARD TYPE 'MR' AT ALL WET LOCATIONS. STOP 'MR' BOARD 1/2" ABOVE FLOOR LINE.
 4. SEE SHEETS LIFE SAFETY SHEETS FOR LOCATION OF RATED PARTITIONS.
 5. TYPICAL COLUMN SURROUND: SEE DETAIL 6/A8.0.
 6. INSTALL ALL DOORS WITH MINIMUM 18 INCHES CLEAR FROM INSIDE FACE OF LATCH SIDE OF JAMB TO FINISH FACE OF WALL ON PULL SIDE OF DOOR.
 7. AT UNASSIGNED SPACES, INSTALL GYPSUM WALL BOARD BUT DO NOT TAPE OR PAINT. WHERE THE UNASSIGNED SPACES ADJOINS A RATED WALL, THE RATED WALL MUST BE FIRE TAPED, BUT NOT PAINTED.
 8. IT IS THE RESPONSIBILITY OF EACH CONTRACTOR TO PROVIDE COMPLETE WORKING SYSTEMS FOR NEW ELEMENTS.
 9. ALL CONTRACTORS SHALL PROVIDE NEW, UNMOUNTED MATERIALS UNLESS OTHERWISE SPECIFIED.
 10. STORE MATERIALS IN SUCH A MANNER AS NOT TO OVERSTRESS, OVERLOAD, OR OTHERWISE PUT AN UNSAFE LOAD ON ANY STRUCTURE DURING CONSTRUCTION.
 11. INSTALL ALL WORK IN ACCORDANCE WITH CURRENT APPLICABLE CODES, PUBLISHED STANDARDS, AND ACCEPTABLE CONSTRUCTION STANDARDS.
 12. ALL NEW WORK SHALL BE PLUMB AND LEVEL UNLESS OTHERWISE NOTED.
 13. ALL SMOKE RESISTANT CONSTRUCTION SHALL EXTEND TO STRUCTURE ABOVE OR ENCLOSED CEILING. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR EXTENDING PARTITIONS AROUND EQUIPMENT CABINETS AND OTHER ITEMS WHICH PENETRATE THESE PARTITIONS, AND SHALL BE RESPONSIBLE FOR FILLING ALL VOIDS IN PARTITIONS ABOVE CEILING, IN ORDER TO MAINTAIN DESIGNATED SMOKE RESISTANCE.
 14. DISSIMILAR FLOOR MATERIALS SHALL MEET UNDER CENTER OF DOOR LEAF, UNLESS NOTED OTHERWISE.
 15. EACH CONTRACTOR SHALL COORDINATE THEIR WORK WITH ALL OTHER TRADES.
 16. DO NOT SCALE DRAWINGS TO DETERMINE DIMENSIONS. IF A REQUIRED DIMENSION IS NOT INDICATED, CONTACT THE ARCHITECT FOR DETERMINATION.
 17. DETAILS ARE GENERALLY TYPICAL AND ARE NOT TO BE CONSTRUED AS LIMITED TO THOSE AREAS SPECIFICALLY INDICATED. REVIEW ANY QUESTIONS OR CONFLICTING INFORMATION WITH THE ARCHITECT PRIOR TO INSTALLATION.
 18. THE CONTRACTOR SHALL NOT CUT STRUCTURAL MEMBERS/ELEMENTS IN A MANNER RESULTING IN A REDUCTION OF LOAD CARRYING CAPACITY OR LOAD/DEFLECTION RATIO.
 19. PROVIDE FRP PANELS AT ALL MOP SINKS. EXTEND MATERIAL A MINIMUM OF 18" WIDER THAN SINK AND AT LEAST 48" A.F.F.
 20. BULKHEAD HEIGHT SHALL BE 2" LOWER THAN THE LOWEST ADJACENT CEILING.
 21. FIELD VERIFY COLUMN SIZES/LOCATIONS FOR ANY CASEWORK INTERFERENCE.
 22. PROVIDE STAINED AND SEALED CONCRETE AT ALL INTERIOR CONCRETE LOCATIONS, SEE SPECIFICATIONS. OMIT STAIN AT MAINTENANCE AREA.

Architectural Symbology

Scale: Not To Scale

A.B. (s)	ANCHOR BOLT(S)	FLSHG.	FLASHING	PL.	PLATE
A.C.	AIR CONDITIONER	FLOUR.	FLOURESCENT	PLAST. LAM.	PLASTIC LAMINATE
A.F.F.	ABOVE FINISHED FLOOR	FLOOR.	FLOOR	PLBG.	PLUMBING
ACOUS.	ACOUSTIC(AL)	FRMG.	FRAMING	PLYWD.	PLYWOOD
ACT.	ACOUSTIC(AL) TILE	FT.	FOOT/FEET	PNL(S)	PANEL(S)
ADTL	ADDITIONAL	FTG.	FOOTING	PNT.	PAINT
AGG.	AGGREGATE	FUR.	FURRING	PR.	PAIR
ALT.	ALTERNATE			PTD.	PAINTED
ALUM.	ALUMINUM	G.C.	GENERAL CONTRACTOR	R.O.	ROUGH OPENING
APPROX.	APPROXIMATE(LY)	GA.	GAUGE	R.S.	ROUGH SAWN
ASPH.	ASPHALT	GALV.	GALVANIZED	RAD.	RADIUS
		GENL.	GENERAL	REC.	RECESSED
B/O	BOTTOM OF	GL.	GLASS	REINF.	REINFORCED
BLDG.	BUILDING	GR.	GRADE	REQD.	REQUIRED
BLKG.	BLOCKING	GYP.	GYPSUM	REV.	REVISED (REVISION)
BOT.	BOTTOM	H.C.	HEATING CONTRACTOR	RM.	ROOM
BRG.	BEARING	H.M.	HOLLOW METAL	RTNG.	RETAINING
C	CENTERLINE	HD.	HEAD	S	SOUTH
C/C	CENTER TO CENTER	HDWR.	HARDWARE	S.B.	SPLASH BLOCK
C.J.	CONTROL JOINT	HOL.	HOLLOW	S.F.	SQUARE FEET
C.L.L.	CONTRACT LIMIT LINE	HOR.	HORIZONTAL	S.S.	STAINLESS STEEL
CEM.	CEMENT(ITI)OUS	HT.	HEIGHT	SAN.	SANITARY
CMU	CONCRETE MASONRY UNIT	IDPH	ILLINOIS DEPARTMENT OF PUBLIC HEALTH	SHT.	SHEET
CLG.	CEILING	I.D.	INSIDE DIAMETER	SHTG	SHEATHING
CLKG.	CAULKING	IN.	INCH	SIM.	SIMILAR
CLR.	CLEAR	INCLD.	INCLUDING	SPEC.	SPECIFICATIONS
COL.	COLUMN	INSUL.	INSULATION	SFG.	SPACING
CONC.	CONCRETE	INT.	INTERIOR	SO.	SQUARE
CONST.	CONSTRUCTION	JAN.	JANITOR	STD.	STANDARD
CONTIN.	CONTINUOUS	JST.	JOIST	STL.	STEEL
CPT.	CARPET	JT.	JOINT	STOR.	STORAGE
CTRFLSHG.	COUNTERFLASHING	LAV.	LAVATORY	STRUC.	STRUCTURAL
		LB(S)	POUND(S)	SUSP.	SUSPENDED
D.F.	DRINKING FOUNTAIN	LT.	LIGHT	T&G	TONGUE AND GROOVE
D.S.	DOWNSPOUT	M.O.	MASONRY OPENING	T/O	TOP OF
DBL.	DOUBLE	MAS.	MASONRY	TELE.	TELEPHONE
DEG.	DEGREE	MATL.	MATERIAL	TH.	THICKNESS
DET.	DETAIL	MAX.	MAXIMUM	THR.	THRESHOLD
DIA.	DIAMETER	MECH.	MECHANICAL	TRTD.	TREATED
DIM.	DIMENSION	MFR.	MANUFACTURER	TS.	TUBE STEEL
DN.	DOWN	MIN.	MINIMUM	TYP.	TYPICAL
DRN.	DRAIN	MTD.	MOUNTED	UNFIN.	UNFINISHED
DTL.	DETAIL	MTL.	METAL	V.	VENT
DWG(S)	DRAWING(S)	N	NORTH	V.C.J.	VERTICAL CAULKED JOINT
DWL(S)	DOWEL(S)	N.I.C.	NOT IN CONTRACT	VCT.	VINYL COMPOSITION TILE
		N.T.S.	NOT TO SCALE	VENT.	VENTILATOR
E	EAST	NOM.	NOMINAL	VERT.	VERTICAL
E.C.	ELECTRICAL CONTRACTOR	O.C.	ON CENTER	W	WEST
EHO	ELECTRICAL HOLD OPEN	O.D.	OUTSIDE DIAMETER	W(O)	WITH(OUT)
E.J.	EXPANSION JOINT	OP	PUSH BUTTON OPERATOR	W.C.	WATER CLOSET
E.W.	EACH WAY	O. TO O.	OUT TO OUT	W.GL.	WIRED GLASS
EA.	EACH	OPNG.	OPENING	W.W.F.	WELDED WIRE FABRIC
EIFS.	EXTERIOR INSULATION FINISH SYSTEM	OPP.	OPPOSITE	WD.	WOOD
EL.	ELEVATION	OVHD.	OVERHEAD	WT.	WEIGHT
ELEC.	ELECTRICAL	P.C.	PLUMBING CONTRACTOR		
ELEV.	ELEVATOR	P.E.B.	PRE-ENGINEERED BUILDING		
EQ.	EQUAL	P.J.F.	PERFORMED JOINT FILLER		
EQUIP.	EQUIPMENT	P.T.	PRESERVATIVE TREATED		
EXIST.	EXISTING	PART.	PARTITION		
EXT.	EXTERIOR	PERIM.	PERIMETER		
F.D.	FLOOR DRAIN				
F.E.	FIRE EXTINGUISHER				
F.E.C.	FIRE EXTINGUISHER CABINET				
FBRGLS.	FIBERGLASS				
FDN.	FOUNDATION				
FIN.	FINISH				

Architectural Abbreviations

Scale: Not To Scale

ISSUE:
Date: Description:

PROJECT:
Peoria Housing Authority

Harrison Homes Redevelopment

Peoria, IL

Date: 07-09-09

Design/Drawn: JRC/KLD

Reviewed: EJB

Book No.: -

SYMBOLS ABBREV NOTES

SHEET NUMBER:

A0.1

SHEET - OF -

Project No.: 0090282.00

XRef Files: J:\peoria housing authority\2009\0090282.00-pha - harrison phase 2 office & seniors.dwg\sheet\0090282.00-aa SYMBOLS ABBREV NOTES.DWG | DATE: 07/01/2009 | Time: 11:18 | J:\peoria housing authority\2009\0090282.00-pha - harrison phase 2 office & seniors.dwg\sheet\0090282.00-aa SYMBOLS ABBREV NOTES.DWG | DATE: 07/01/2009 | Time: 11:18 |